ENGINEER'S OPINION OF PROBABLE COST

CLIENT	CITY OF FORNEY				
PROJECT	EXTENSION OF TRAILHOUSE ROAD SOUTH OF EMERSON APTS TO HWY 80				
	PHASE TWO - SANITARY SEWER				
DATE:	12-Feb-20				
	Item	Qty.	Unit	Unit Cost	Total Cost
	MOB AND DEMOB	1	LS	\$10,000.00	
	BONDING & INSURANCE	1	LS	\$20,000.00	
	18" SEWER LINE	985	LF		\$ 93,575.00
S4	18" SEWER ENCASED IN BORE	290	LF	\$ 625.00	\$181,250.00
	18" SEWER IN CONCRETE ENCASEMENT	25	LF	\$ 120.00	\$ 3,000.00
S6	5' Dia MANHOLES WITH LINING	6	EA	\$17,800.00	\$106,800.00
S7	5' Dia MANHOLES WITH LINING ON EXISTING	1	EA	\$18,600.00	\$ 18,600.00
	ADDITIONAL VERTICAL DEPTH 5' DIAMETER MANHOLES	40	LF	\$ 600.00	\$ 24,000.00
S9	CONNECT NEW SEWER TO EXISTING SEWER (UPSTREAM)	1	LS	\$ 2,000.00	\$ 2,000.00
S10	CONNECT EXISTING SANITARY SEWER SERVICES	2	EA	\$ 2,400.00	\$ 4,800.00
S11	EROSION CONTROL	1	LS	\$ 4,000.00	\$ 4,000.00
S12	REPAIR & REPLACE EXISTING RIP RAP	1	LS	\$ 2,200.00	\$ 2,200.00
S13	HYDROMULCH	2100	SY	\$ 1.50	\$ 3,150.00
S14	CRUSHED ROCK FOR PIPELINE BOTTOM STABILITY	100	CY	\$ 42.00	\$ 4,200.00
S15	TRENCH SAFETY	985	LF	\$ 2.50	\$ 2,462.50
	SUBTOTAL				\$480,037.50
PAVING					
P1	REMOVE EXISTING PAVEMENT & CURB	1,106	SY	\$15.00	\$16,590.00
	REMOVE EXISTING DRIVEWAYS	161		\$15.00	\$2,415.00
P3	6" 3600 PSI CONC PVMT WITH NO. 4 ON 18" E.W.	1,108		\$56.00	\$62,048.00
P4	6" ROLLBACK CURB	470	LF	\$2.00	\$940.00
P5	6" LIME STABILIZED SUBGRADE	1,217	SY	\$6.00	\$7,299.60
P6	HYDRATED LIME (32 LBS/SY)		TN	\$180.00	\$7,200.00
P7	CONCRETE DRIVEWAY REPLACEMENT	161	SY	\$70.00	\$11,270.00
P8	CONCRETE SIDEWALK REPLACEMENT		SY	\$45.00	\$90.00
P9	SODDING		SY	\$7.00	\$770.00
P10	LONGITUDINAL BUTT JOINT	12	LF	\$10.00	\$120.00
P11	TRAFFIC CONTROL THRU CONSTRUCTION	1	LS	\$8,000.00	\$8,000.00
	SUBTOTAL				\$116,742.60
TOTAL PROBABLE CONSTRUCTION COST				_	\$596,780.10
ENGINEERING/SURVEY				\$ 41,770.00	
MATERIAL TESTING 5%				\$ 29,840.00	
CONTINGENCY (10%)					\$ 59,680.00
LAND ACQUISTIONS/EASEMENTS				\$ -	
RECOMMENDED PROJECT BUDGET (COMPLETION OF PHASE TWO OF TRAILHOUSE PROJECT)					\$728,070.10